

gr	avi	ee
<u> </u>	One-Ste	p Wall System

© 2022





#### **Order #XXXXX** General Information



# **General Setup Instructions**

© 2022

- Read entire setup instruction manual prior to unpacking parts and pieces.
- The setup instructions are created specifically for this configuration.
- Setup instructions are laid out sequentially in steps, including exploded views with detailed explanation for assembly.

# **Cleaning & Packing**

- For Cleaning Metal, Plex, & Laminate Parts: Use a MILD NON-ABRASIVE cleanser and soft cloth/paper towel to clean all surfaces.
- Keep exhibit components away from heat and prolonged sun exposure. Heat and UV exposure will warp and fade components.
- Retain all provided Packing Materials. All provided packing materials are for ease of repacking & component protection.

## Disassembly

- For loss prevention, tighten all set screws and locks during disassembly.



#### Assembly Cont'd



# Side-by-Side Assembly

1) Frames: Place frames side-by-side with one higher than the other, then slide panel down to lock panels securely together.

2) Corner Connectors: Repeat Step 1 for installing corner connectors to frames.

## **SEG Graphic Installation**



It is important to first insert graphic into each alternate corner, then to the sides of the frame If this is not done, graphic will not fit into the frame correctly



Step 1 Insert corner A Turn edge of graphic so silicon welt is perpendicular to face of graphic. Insert narrow side of welt with fabric to outside into the channel. Repeat for other side of this corner



Step 2 Repeat Step 1 for opposite corner C, then insert corner B, followed by corner D, to complete the installation of the corners



Step 3 Once all corners are inserted, press one silicon edge into channel from corners and work toward the center. Make sure welt is fully inserted into channel. Continue until all sides are

# Side-by-Side Disassembly

1) Pull pin lock outwards to disengage.

2) Pull frames upward and apart at the same time to detatch.

done. Smooth out edges of graphic.

**Graphic Removal** 



To remove the graphic from the frame, locate the fabric pull tab. Gently pull up on the tab to remove the fabric.

gravitee One-Step Wall System

# **Corner Bracket Assembly**

© 2022

- Slide TWO-PIECE TS RV 2 L-bracket into Interior Center Slot of extrusion so that two set screws are inside groove. Tighten two set screws to secure.
- 2) Slide one A1 L-Bracket into outer interior grooves of upper and lower horizontals. Tighten set screws to secure.
- Slide vertical extrusion over exposed ends of brackets in lower horizontal. Tighten set screws to secure.
- Slide exposed ends of installed brackets of upper horizontal into open ends of verticals. Tighten set screws to secure.

## Disassembly

1) Loosen set screws on brackets and slide extrusions off of brackets.



# **Straight Bracket Assembly**

- 1) Slide TWO-PIECE TS RV 4 straight bracket into Interior Center Slot of extrusion, so that two of the set screws are inside groove. Tighten two set screws to secure.
- 2) Slide one V4 Connector into outer interior groove of extrusion, so that one set screw is inside groove. Tighten set screw.
- 3) Slide connecting extrusion over exposed ends of bracket & connector. Tighten all remaining set screws to secure extrusions.







#### Order #XXXXX GK-2012 Lightbox Assembly



© 2022





### Completed Assembly

- Base Plate 1,1
- 2
- 1
- 1
- 1
- 1
- 1



- and wing nuts.
- See Gravitee Assembly Instruction sheet for details.
- See Lightbox Attachment detail.

### Keep S44 verticals attached to Gravitee panels [3] [13] [9] and [10].







#### Order #XXXXX Modified MOD-1700 Cabinet

Item	Qty.	Description
1/1A	1/1	46.25" CEI-110 Horizontal Extrusion
2/2A	1/1	37.5" CEI-110 Vertical Extrusion
3/3A	1/1	37.5" S44 Vertical Extrusion
4	1	37.5" S44 Vertical Extrusion w/Door Hinges
5	1	37.5" S44 Vertical Extrusion w/Door Stops
6	1	37.5" S44 Vertical Extrusion w/Door Hinges
7/7A	2/2	14.153" Z45 Horizontal Extrusion
8/8A	2/2	20.408" Z45 Horizontal Extrusion

© 2022

#### Steps:

- 1) Assemble frame extrusions [1,1A,2,2A]. See CEI-110 Frame Assembly sheet.
- 2) Connect lights and transformer. See Light to Light Connection and Light to Transformer Connection details.
- 3) Attach horizontal extrusions [7] & [8] between vertical extrusions [3,3A,4,5,6].
- 4) Slide infills between vertical extrusions [3,4] & [3A,6].
- 5) Connect doors between vertical extrusions [4,5] & [5,6]. See Door Connection detail.
- 6) Attach horizontal extrusions [7A] & [8A] between vertical extrusions [3,3A,4,5,6] and on top of infills and doors.
- 7) Connect shelf supports to Velcro on inside of infills and insert pins to vertical extrusions [3] [3A] & [5]. See Shelf Pin detail.



CEI-110 Frame Assembly











#### **Order #XXXXX** Modified MOD-1700 Cabinet (Cont'd)

#### Steps:

1) Connect light blocker to Velcro on interior of assembled frame.

© 2022

- 2) Attach assembled frame to verticals [3] and [3A]. See Frame Attachment detail.
- 3) Install SEG graphic to front of assembled frame. See SEG Graphic Installation detail.
- 4) Place shelf inside assembled base on top of pins and supports.
- 5) Place counter top on assembled base, then secure with pins. See Counter Top Attachment detail









## **SEG Graphic Installation**



It is important to first insert graphic into each alternate corner then to the sides of the frame. If this is not done, graphic will not fit into the frame correctly.



Step 1 Insert corner A. Turn edge of graphic so silicon welt is perpendicular to face of graphic. Insert narrow side of welt with fabric to outside into the channel. Repeat for other side of this corner.



Repeat Step 1 for opposite corner C, then insert corner B, followed by corner D, to complete the installation of the corners.



out edges of graphic

Once all corners are inserted, press one silicon edge into channel from corners and work toward the center. Make sure welt is fully inserted into channel. Continue until all sides are done. Smooth

